Sl. No.	Descriptions	Unit
1	KSRRB 200 Cutting of trees KSRRB 200-1, Cutting of trees girth from 300mm to 600mm including cutting of trunks, branches and removal of stumps stacking of serviceable materials earth filling in the depressions / pit, labour charges complete as per specification .MORTH specification clause complete as per specifications as per specifications and directions of engineer in charge of the work	Sqm
2	Dismantling burnt brick masonry in clay mortar / lime mortar / cement mortar and stacking the bricks within a radius of 50 m and removing the debris to a distance upto 200m, complete as per specifications as per specifications and directions of engineer in charge of the work	Cum
3	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50 m and removing the debris to a distance upto 200m, complete as per specifications as per specifications and directions of engineer in charge of the work	Cum
4	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, complete as per specifications as per specifications and directions of engineer in charge of the work	cum
5	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km complete as per specifications as per specifications and directions of engineer in charge of the work	Cum
6	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305.complete as per specifications as per specifications and directions of engineer in charge of the work	Cum
7	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications complete as per specifications as per specifications and directions of engineer in charge of the work	Cum
8	KSRB-4-1.3 : Providing and laying in position **plain cement concrete of mix M 7.5** withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, complete as per specifications as per specifications and directions of engineer in charge of the work	cum
9	KSRB 5.2-2 Providing and constructing granite / trap / basalt rubble **stone masonry in foundation** with mud mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per specifications as per specifications and directions of engineer in charge of the work	cu
10	KSRB 5.3-3 Providing and constructing granite / trap / basalt **size stone masonry in basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per specifications as per specifications and directions of engineer in charge of the work	cur
11	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification complete as per specifications as per specifications and directions of engineer in charge of the	c
12	Providing **flush pointing** to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. complete as per specifications as per specifications and directions of engineer in charge of the work	sc
13	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. complete as per specifications as per specifications and directions of engineer in charge of the work	C